

The auction sale should be confirmed by the Assistant Director, Bangalore Circle, Bangalore. The crop of trees other than the mango trees are solely reserved for the school. The person in whose favour the auction sale is confirmed should execute a bond with the Head Master, R. K. Sala, that he would not cut any trees for fuel or damage them in any manner.

B. DASAPPA,
Assistant Director.

OFFICE OF THE AGRICULTURAL ENGINEER, BANGALORE.

Notification No. 5 of 1938-39, dated 12th March 1939.

Notice is hereby given that sealed tenders will be received at the Office of the Agricultural Engineer up to 2 P.M. on 8th April 1939 for constructing a poultry house at the Rural Welfare Centre at Closepet.

2. An approximate estimate of quantities for the above work is given below. These quantities are not guaranteed. The work should be completed within one month from the date of acceptance of tender.

3. Earnest money of Rs. 60 in cash should be remitted under Revenue Deposit at the State Huzur Treasury, Bangalore, with a challan duly filled in by tenderers. The tender should be superscribed 'Constructing a poultry house at the Rural Welfare Centre at Closepet.' The tenders will be opened at 2-30 P.M. on 8th April 1939.

4. Subject to the formal sanction of the Director of Agriculture, the acceptance of any tender rests with the Agricultural Engineer who does not bind himself to accept the lowest or any tender or assign any reason whatsoever for the rejection of any tender.

5. Within a week of the acceptance of the tender, the successful tenderer will be required to furnish a cash security of five per cent of the value of the work and to execute the usual contract bond in default of which his tender will be considered as cancelled and the security deposit forfeited.

6. The name of the successful competitor whose tender has been accepted will be notified in due course.

7. After the acceptance of the successful tender the earnest money deposited on the refused tenders will be arranged to be returned to the parties.

8. Rates over the tendered rates will on no account be enhanced.

9. Quotations must be written in words as well as in figures.

10. The measurements checked by the Agricultural Engineer will have to be accepted as final.

Approximate quantity of works.

1. Earthwork excavation for foundation	12 Cyds.
2. Stone in mud	484 C.ft.
3. Brick in mud	734 "
4. Brick in mortar	149 "
5. Stone slab 6" thick roughly dressed	17 S.ft.
6. Do 4" neatly dressed	41 S.ft.
7. Roofing with cement asbestos sheets	7.4 Squares
8. Ridge with asbestos sheets	32 R.ft.
9. Teakwood doors, with fully panelled 1½" thick and iron fittings	23 S.ft.
10. Teakwood doors with half panelled and half expanded metal	23 S.ft.
11. Teakwood windows with battened shutters and glazed shutters, iron bars complete	24 "
12. T. W. Rectangular ventilator with glazed shutters with iron bars complete	7½ "
13. Flooring with 1½" cement concrete on 4" lime concrete with a coat of cement plaster	4.4 Sqs.
14. Chunam Plastering	14.6 Squares
15. White Washing	16.0 "
16. Painting with green	1.7 "
17. Providing expanded metal ½" mesh on T. W. frame work	94 S.ft.
18. Filling the basement	16 Cyd.
19. Pointing with cement	1 square
20. T. W. Eve Board	64 R.ft.
21. Iron Trusses for a clear span of 15'	1
22. Angle Iron purlins 1½" x 1½" x ¼"	4 Cwt.
23. Mortar-Bond including ornamental cornice	90 R.ft.
24. Fitting purlins and trusses in cement 1' x 1½' x 1'	11 Nos.
25. T. W. Finials at bottom	4 Nos.
26. Cement concrete	4 C.ft.
27. Plastering with concrete	2 Squares
28. T. W. wrought and put up	3.5 C.ft.

N.B.—Mysore Cement will have to be used and will be supplied departmentally.

M. G. SINGARACHAR,
Agricultural Engineer.